



NOTES

1. Verify color, pattern, and style of pavers with City before ordering and again before laying.
2. When compacting subgrade, any area that settles excessively and fails to stabilize under continued compaction should be further undercut and replaced with properly compacted select granular fill.
3. Install 1/2" expansion joint at 30' on center.



Department of Public Works
10455 Armstrong Street
Fairfax, VA 22030-3630

CITY of FAIRFAX
USE WITH THE FAIRFAX STANDARD SPECIFICATIONS ONLY

Voice (703) 246-6330
FAX (703) 591-5727
www.fairfaxva.gov

**TYPICAL CONCRETE PAVERS
SIDEWALK DETAIL**

SCALE:
Not To Scale

DETAIL #
2406.01

REVISION DATE:
July, 2005

SHEET #:
1 of 1